



Kerala Transport Development Finance Corporation Ltd Trans Towers (6th Floor), Vazhuthacaud, Thiruvananthapuram,
Telephone: 0471-2327881, 2326883, web: www.ktdfc.com

Tender Notice

Tender No. 30 /KTDFC/BOTP/KKD/2019

Name of Work	Period of completion	EMD	Cost of Tender form	Estimated PAC
Civil works of shifting the lifts to the 1st basement floor from II nd basement floor in KSRTC Bus Terminal Complex Kozhikode	one month	Rs.2700	Rs. 500 plus 18% GST = Rs. 590	Rs. 1,05,000

Sealed Competitive Tenders are invited for the work of **Civil works of Shifting the lifts to the first basement floor from II nd basement floor in KSRTC Bus Terminal Complex Kozhikode** . Tender forms will be available at the KTDFC website **www.ktdfc.com** from **6.04.2019** . Last date of receipt of tender will be **22.04.2019** at 11am. Tender will be opened on **22.04.2019** at 11.30 am .

For more details please visit **www.ktdfc.com**

For any further details, please contact KTDFC (Ph: **0471 2327881**).

Date: **5.4.2019**

Principal Project Consultant

Tender Schedule

Name of work : **Civil works of shifting the lifts to the Ist basement floor from II nd basement floor in KSRTC Bus Terminal Complex Kozhikode**

Estimated PAC : Rs.1.05 lakhs

Sl No	Description	Unit	Quantity	Rate
1	Demolishing R.C.C work manually /by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per the direction of engineer in charge 15.3	m3	0.25 m3	
2	Reinforced Cement concrete :1.5:3 using 20mm size hard granite broken stone for bottom beams of tank includng all form work, watering, curing, cost and conveyance of all materials and labour charges etc upto plinth level.complete but excluding reinforcement 5.3	m3	0.75m3	
3	Reinforced Cement concrete :1.5:3 using 20mm size hard granite broken stone for columns of tank including all form work, watering, curing, cost and conveyance of all materials and labour charges etc upto plinth level complete but excluding reinforcement 5.2	m3	2.55m3	
4	Centering and shuttering including strutting, propping etc and removal of form for all heights for beams including all form work, watering, curing, cost and conveyance of all materials and labour charges 5.9.5	m2	4.7m2	
5	Centering and shuttering including strutting, propping etc and removal of form for all heights for columns including all form work, watering, curing, cost and conveyance of all materials and labour charges 5.9.6	m2	22.5m2	
6	Plastering with cement mortar 1:3, 6mm thick one coat floated hard and trowelled smooth including watering , curing, cost conveyance of all materials and labour charges etc complete 13.16.1	m2	25m2	
7	Structural steel work riveted, bolted or welded in built up sections, framed work, including cur=ting, hoisting, fixing in position, cost and conveyance of all materials and labour charges and applying a priming coat of approved seel primer all	kg	411 Kg	

	complete 10.2			
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work including all cost and conveyance of all materials and labour charges 13.6.1.1	kg	21kg	
	Total			

Total

Rupees

.....

Principal Project Consultant